



Grant County
Department of Public Works
124 Enterprise St. S.E.
Ephrata, WA 98823



Serial No. 11-048

Memo

To: ALL PLAN HOLDERS

From: Jeff Tincher, P.E.
Assistant County Road Engineer 

Date: February 16, 2011

Re: **R-NE Road**
CRP 08-13 & 10-05
RAP Project #1307-02

ADDENDUM #1

The Special Provisions, Plans & Proposal for this project are amended as follows:

Special Provisions

The following Special Provisions are changed, added and/or supplemented:

Borrow

Section 2-03.3(13) is supplemented with the following:

The Scalping pile at Pit Site #87, Mordhorst Pit, Sec 6, T22N, R30E W.M. is provided as a borrow site for this project. There is no cost for this material.

The unit contract price bid per cubic yard for "Borrow Excavation incl. Haul" shall be full compensation for performing the work outlined herein and in accordance with the plans and specifications.

Plans

The following Plan Sheet's are changed, added and/or supplemented:

Sheet #15

Structure Note #1 shall be changed from Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 72" x 44" to **Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 66" x 51"**. The bottom of pipe elevation shall be changed from 1548.00 to **1547.35**.

Sheet #17

Structure Note #1 shall be changed from Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 65" x 40" to **Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 60" x 46"**.

Sheet #19

The attached Roadway Section shall be added from Station 79+50 to Station 82+00.

Proposal

The following Bid Item's are changed, added and/or supplemented:

Bid Item #7

Roadway Excavation including Haul, the quantity shall be changed from 23,417 C.Y. to **23,559 C.Y.** The quantity was revised per the added roadway section.

Bid Item #14

The Item Description shall be changed from Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 65" x 40" to **Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 60" x 46"**.

Bid Item #15

The Item Description shall be changed from Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 72" x 44" to **Plain Steel Culvert Pipe 0.109" Th., 5x1 Corr., 66" x 51"**.

The appropriate location on the proposal will need to be marked to acknowledge receipt of this Addendum.

"TO MEET CURRENT AND FUTURE NEEDS, SERVING TOGETHER WITH PUBLIC AND PRIVATE ENTITIES,
WHILE FOSTERING A RESPECTFUL AND SUCCESSFUL WORK ENVIRONMENT."

Information.....(509) 754-6082
FAX.....(509) 754-6087
E-mail..... publicworks@co.grant.wa.us
Derek Pohle, P.E., Director/County Engineer.....Ext. 3504
Dave Heilman, Assistant Director.....Ext. 3502

Jeff Tincher,P.E., Assist. County Rd. Engineer.....Ext. 3519
Bob Bersanti, Construction Engineer.....Ext. 3503
Malissa Curran, Accountant.....Ext. 3555
Rod Follett, Foreman-Sign Shop.....Ext. 3579
Janice Goeden, Solid Waste.....(509) 754-4319

Steve Hill, Supervisor-Dist. No. 1.....Ext. 3539
Dennis Collier, Supervisor-Dist. No. 2.....(509) 765-4172
John Brissey, Supervisor-Dist. No. 3.....(509) 787-2321
Darrell Doolittle, Supervisor-Central Shop.....(509) 754-6086
Jerome Wawers, Bridge Supervisor.....Ext. 3535

ROADWAY SECTION

STA. 79+50 = 82+00

