



Grant County
Department of Public Works
 124 Enterprise St. S.E.
 Ephrata, WA 98823



Serial No. 14-176

MEMO

To: ALL PLAN HOLDERS
From: Todd Mittge, P.E. *(Signature)*
 Assistant County Road Engineer
Date: September 11, 2014
Re: Adams Road Overlay Project, CRP 14.01

ADDENDUM #1

The Special Provisions for this project are amended as follows:

Special Provisions

The following Special Provisions are changed, added and/or supplemented:

Page 69, Line 33, the following is inserted:

5-04.3(5)A, Preparation of Existing Surfaces

Section 5-04.3(5)A is supplemented with the following:

(*****)

Approximately 195 Linear Feet of Type D Plastic Transverse Rumble Strips and 13 Each Plastic Traffic Letters (Approximately 3' Wide X 8' Long) are located on Adams Road South of the SR 283 Intersection. The Contractor shall remove these Plastic rumble strips and letters to original pavement condition prior to tack coat and HMA Overlay. Removal may be by torch/scrapper, grinder, or other method proposed by the Contractor and approved by the Engineer. All costs associated with the described work will be incidental to, and included in the bid item, "HMA Cl. 1/2 In. PG64-28".

Page 70, Lines 4-7 are deleted and replaced with the following:

- If the proposed mix design has not been referenced and previously verified by WSDOT State Materials Lab on a previous project, the Contractor shall also submit samples to the WSDOT State Materials Lab for WSDOT verification testing in accordance with WSDOT Standard Specifications.

The appropriate location on the proposal will need to be marked to acknowledge receipt of the Addendum.

Attachments: None

"To meet current and future needs, serving together with public and private entities, while fostering a respectful and successful work environment."