

**ADDENDUM NO. 2**

June 23, 2011

The following addendum items shall become part of the Contract Documents for the above referenced project.

**GENERAL**

**Item No. 1:** Addendum No 1, Item No.5: The concrete panels currently identified as pre-cast concrete in the Drawings are intended to be tilt-up concrete (specifically around the perimeter of the Office/Shop Building). The specification and details provided in Addendum 1 are in support of that. At the Contractor's option, pre-cast panels may be provided in lieu of the tilt-up concrete panels. Any required engineering for such pre-cast panels shall be accomplished at the Contractor's expense. Panel sizes shall remain the same and finishes specified in the tilt-up specification must be matched.

**PROJECT MANUAL**

**Item No. 2:** Specification Section 015000 - Temporary Facilities and Controls: CLARIFICATION of paragraph 2.1, B. Common-Use Field Office: Drinking water and toilet facilities required for the office do not need to be hard-plumbed into the structure. Bottled water or dispenser and a chemical toilet located nearby are acceptable.

**Item No. 3:** Specification Section 015000 - Temporary Facilities and Controls: CLARIFICATION of paragraph 3.2, H. and I., Telephone and Electronic Communications: A cell phone is acceptable for the required telephone line as long as the phone number is made available to all. No separate phone line is required for Owner's Use or for facsimile. E-mail capability is required and necessary for the Electronic Submittal process identified in Section 013300. If no facsimile is provided on site, an email address will be required for contact/information delivery.

**Item No. 4:** Specification Section 017419 - Construction Waste Management and Disposal: DELETE this specification in its entirety. **No specific requirements for waste management will be enforced.** However, participation in any available recycling effort is encouraged, especially in this project for a landfill where diversion of waste would be an example to the public.

**Item No. 5:** Specification Section 095113 – Acoustic Panel Ceilings: MODIFY paragraph 2.2, Acoustic Panels for Acoustic Panel Ceilings as follows:

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong "Fine-Fissured Second Look II" or a comparable product.
- B. Color: White.
- C. LR: Not less than 0.84.
- D. NRC: Not less than 0.55.
- E. Edge/Joint Detail: Angled tegular.
- F. Thickness: 3/4 inch.
- G. Modular Size: 24 by 48 inches.
- H. Antimicrobial Treatment: BioBlock Plus

**Item No. 6:** Specification Section 102800 – Toilet, Bath and Laundry Accessories:

CLARIFICATION: Make the following information for accessories:

- Provide one Seat Cover Dispenser at each water closet location.
- No Mop/Broom Holder is required.
- In addition to other Soap Dispensers and Towel Dispensers, provide one of each at Utility Sink locations.

Verify all location in field with Architect prior to installation.

**DRAWINGS**

**Item No. 7:** Sheet C101, RED/GREEN Traffic Control Light: CLARIFICATION: The new two-color (red and green) light indicated shall closely match the existing light to be relocated. Provide a Red/Green incandescent traffic light, rated for exterior exposure with yellow body and cap-style visors. Include all hardware necessary for mounting to pole. Possible manufacturers include, but are not limited to Rice Lake Weighing Systems or Thurman Scale.

**Item No. 8:** Sheet C500, Typical Sidewalk Detail 1: CLARIFICATION: Sidewalk thickness shall be 4-inches.

**Item No. 9:** Sheet C505, Weigh Scales (Section 1) Detail 2: CLARIFICATION – There is no Specification Section for the vehicle scale. Reference to “scale specification”, as noted, refers to the Make & Model noted in Weigh Scale Plan Layout Detail 1, on this same sheet, (Rice Lake E2 7010-SC100 OTR, with height of 16”). The specification is the design criteria specific to this Make & Model. All materials, fabrication, and installation shall be provided as required to meet all pertinent regulatory requirements. Both scales (the existing to be relocated and the new scale) shall be complete and operational, including all hardware and software required for operation. The new scale shall include a matching operating system, including laptop terminal, as used for the existing scale, or a similar system sufficient for identical operation. The installer for the scale and the operating system shall be approved, as required by the manufacturer of the scale provided. The vendor local to this area has been identified in the Drawings. No pre-approval requests for alternatives were received.

**Item No. 10:** Sheet A101: The Boot Brush identified on the Floor Plan near the main Office/Shop Building entrance shall be Grainger Item #1ETK7 Boot Scrubber, or equivalent.

**Item No. 11:** Sheet A102, Floor Plan, Scale House: CLARIFICATION: The identified 2-ft. square crawlspace access door can be either a pre-fabricated access hatch, or a framed-in-place access panel, at Contractor’s option. Provided panel/hatch shall be sturdy to walk on and without tripping hazard. It must be insulated from crawlspace temperature with minimum R-10 rigid insulation and shall be provided with a recessed handle for removal.

**Item No. 12:** Sheet A301, Section 2 – Shop Building: ADD the Eave Height (Fin. Flr. to top of Eave Strut) dimension at Grid Line 2 as 11’-0”.

**Item No. 13:** Sheet A311, Wall Section C: ADD reinforcing notation to mezzanine floor, as follows: “Minimum 4.4” thick lightweight concrete, with 6x6 W2.9xW2.9 WWF, over structural metal decking”.

**SUBSTITUTION PRIOR APPROVALS**

*Spec Section*

<i>or Drawing No.</i>	<i>Item</i>	<i>Manufacturer and/or Product Accepted</i>
Specification 074113	Metal Roofing Panels	Architectural Metal Solutions (AMS) "Armor-Lock" 24 Ga. 17.7" o.c. w/ Kynar finish <i>(No color chart submitted - Must use color match to those already pre-approved.)</i>
Specification 074113	Metal Soffit Panels	McElroy "Marquee II" 24 Ga. 12" o.c. w/ Kynar finish

END OF ADDENDUM NO. 2